#### Application for Design Review by the County Coastside Design Review Committee

<b>Review Committee</b>	Other Permit #:
Applicant:	Owner (if different from Applicant):
Name: SERHIY KYB Address: 7929 DIAMOND	Name:
ANTELOPE, CAZID: 9. Phone, W: 916-722-1122 H: 916-2	7843 Zip:
Emailyserhiyk@ hotma	il. COM Email:
Architect or Designer (if different fr	om Applicant):
Name: ALEX MARTY	INOVSKIY
Address: 10100 COUNTRYS	PIDE Way Sacramento, CA 95827
Phone,W: H:	SIDE Way Sacrampento, CA 95827  Email: alex.martynovskiy rogmail.com
Project location:	Site Description:
APN: 048-013-600	Vacant Parcel
Address: MAGELLAN AV	
dalf Moon Bay Zip: 9	4019
Zoning:	74/DR
Parcel/lot size: 7,792	sq. ft.
Project:	Additional Permits Required:
New Single Family Residence: 3,	739 sq. ft Certificate of Compliance Type A or Type B
Addition to Residence:	sq. ft Coastal Development Permit
Other:	Fence Height Exception (not permitted on coast)
	Grading Permit or Exemption
Describe Project:	☐ Home Improvement Exception
	□ Non-Conforming Use Permit
	Off-Street Parking Transito W
	□ Variance
	JUL <b>0 6</b> 2015

San Mateo County Planning Division

#### Check if matches Fill in Blanks: **Material** Color/Finish existing (If different from existing, attach sample) Stucco a. Exterior walls b. Trim c. Windows d. Doors e. Roof f. Chimneys g. Decks & railings h. Stairs i. Retaining walls Natural Redwood j. Fences k. Accessory buildings I. Garage/Carport To approve this application, the County must determine that this project complies with all applicable regulations including the required findings that the project does conform to the standards and guidelines for design review applicable to the location of the project pursuant to Section 6565.10. (optional) Applicant's Statement of project compliance with standards and guidelines (check if attached). Thereby certify that the information stated above and on forms, plans, and other materials submitted herewith in support of the application is true and correct to the best of my knowledge. It is my responsibility to inform the County of San Mateo through my assigned project planner of any changes to information represented in these submittals. Applicant: Owner:

Date:

Date:

### Planning and Building Department

#### Application for a **Coastal Development Permit**

Companion Page

455 County Center, 2nd Floor Redwood City, CA 94063 Mail Drop: PLN 122 · TEL (650) 363-4161 · FAX (650) 363-4849 7.2

3.模型 ( *模型	· · · · ·
Applicant's Name:	SERHIY KYBYCH
Primary Permit #:	PLN 2016-00280

#### anothoris

i. Storage Tanks

Please fill out the general Planning Permit Application Form and this form when applying for a Coastal Development Permit, You must also submit all items indicated on the checklist found on the reverse side of the Planning Permit Application Form.

and the state of the same of the same of the same state of the same of the sam		Control Control			Since English
	A PAGE RIVER		tackiek Karasia	ad a samete	dae ava ed Sometare
2. Basic Information					
Does the owner or applicant own any adjacent pristed?		County of San	nyone else prévio Mateo or the Ca	lifornia Coast	al Commission
☐ Yes X No		for a Coastall E at this location	levelopment Peri 7	mit for this or	a similar project
			Yes	X No	
If yes, list Assessor's Parcel Number(s):		If yes, explain	include date and	dapplication	file numbers).
ii yes, iist / 636350i 3 r ai tei Nuimbei jaj.		. ;	•		
			REC	, E. Wit	Former State of the Control of the C
		Const.	nii	0.000	
		The second	- 10 A M. J. W.	<b>V 6</b> 2016	The second of the second of
3. Materials and Finish of P	roposed	Buildine	SOF Sticki		els.
			i tuvu meneden ene		The second se
Note: By completing this section you do not need	·				
อน ประสุทธิ์ การกระบับสมัย และ การกระบับสมัย เป็นสมัย (ค.ศ. พ.ศ. พ.ศ. พ.ศ. พ.ศ. พ.ศ. พ.ศ. พ.ศ.			हर्ग्य <b>अभूमक्षेत्र</b> स्था		
			ATTENDED TO		matches ==== existing
Fill in Blanks: Materia	ľ		Color/Finish	/	101
a. Exterior Walls Stucco			rm Gr	00 1	
b. Trim	1 01	<u> </u>	ou dack	Brue	
c. Roof Coated	Stee	<u> </u>	te stone	O Yay	
d. Chimneys		<u>Pari Perand</u>	<u> </u>	<u> </u>	
e. Accessory Buildings		in the state of th		der er e	
f. Decks/Stairs	Street Street				
g. Retaining Walls	····	<u> </u>	0	·	
h. Fences <u>Redwood</u>	•	1/0	ctural	arijan kanta <del>Turka</del>	
i. Storage Tanks					

Does this project, the parcel on which it is located or the immediate vicinity involve or include:	p. Between the sea and the nearest public road?
a. Demolition of existing housing units? ☐ ☐	q. Existing or proposed provisions for public  access to the shoreline?
(If yes, give value of owner-occupied units or current monthly rent of rental	r. Public or commercial recreation facilities?
units in explanation below.)	t. Existing or proposed public trail
b. Creeks, streams, lakes or ponds?	easements?
c. Wetlands (marshes, swamps, mudflats)?	
d. Beaches?	<b>Explain all Yes answers below.</b> Indicate whether the item applies to the project itself, the parcel on which it is
e. Sand Dunes?	located, or the immediate vicinity (attach additional sheets if
f. Sea cliff, coastal bluffs or blufftops?	necessary): m.Phowe, electricity
h. Pampas Grass, invasive brooms or Weedy Thistle?	n. tsunami zone ?
i. Removal of trees or vegetation?	
j. Grading or alteration of landforms?	
k. Landscaping?	
I. Signs?	
m. Phone or utility line extensions or connections, either above or below ground (explain which)?	
n. Areas subject to flooding?	
o. Development on slopes 30% or steeper?	
The second secon	The second of the contract of the contract of the second of the contract of th
5. Staff Use Only	
California Coastal Commission Jurisdiction	Commission; a public hearing is always required.
A. Does the Proposed Project Involve:	<b>B.</b> Does the proposed project involve lands below the mean
1. A subdivision, Certificate of Compliance Type B, Use Permits of Planned Agricultural District Permit?  Yes	high tide line and lands where the public trust may exist? (See "Post CCP Certification Permit and Appeal Jurisdiction Map).
	Yes Your No
2. Construction or grading within 100 feet of a stream or wetland?  □ Yes □ No	Yes to above means that the California Coastal Commission
3. A parcel located between the sea and the first public through road paralleling the sea; 300 feet from the inland extent of any beach or mean high tide line if there is no beach; or within 300 feet of the top of the seaward face of	retains permit jurisdiction over all or part of the proposed project. A Coastal Development Permit from that agency is required.
a coastal bluff?   Yes  No	Reviewed by:
Yes to any one of the above means that the Coastal  Development Permit is appealable to the Coastal	

Env	/iron	mental Information ure Form	County of San Mateo  PLN  BLD
Assess Zoning Parcel s Describ	District:	ELLAN AVE  non BAY, CA 94019  cel No.: 048 - 013 - 600  Z-1/ T	Name of Owner: SERHIY LYBYCH  Address: 7929 Diamond Rock Dr., ANTELOPE  CA. 95 843 Phone: 916 - 214 - 5461  Name of Applicant: SERHIY LYBYCH  Address: 7929 Diamond Rock Dr., ANTELOPE  CA. 95 843 Phone: 916 - 214 - 5461  and uses on the project parcel, including the existence and of any natural features on the project parcel (i.e. steep terrain,
DOM: AND DESCRIPTION OF THE PERSON OF THE PE	estation constitutions	nental Review Checklist	
Yes	No	Will this project involve:	A) Review
	<del> </del>		9/ of the orieties are OD - 0.500 - 60
	1	a. Addition to an existing structure > 50     b. Construction of a new multi-family res	idential structure having 5 or more units?
	-	c. Construction of a commercial structure	
	7		n. in Emerald Lake Hills area or ≥ 12" d.b.h. in any
	<b>/</b>	e. Land clearing or grading?  If yes, please state amount in cubic y Excavation:  c	ards (c.y.): .y. Fill:c.y.
	>	f. Subdivision of land into 5 or more par	
	r ><	g. Construction within a State or County	scenic corridor?
		h. Construction within a sensitive habitat	?
$\times$		i. Construction within a hazard area (i.e	. seismic fault, landslide, flood)?
	$\geq \leq 1$	j. Construction on a hazardous waste si	te (check with Co. Env. Health Division)?
Please	explain	all "Yes" answers:	

Signature <u>required</u> on reverse →

RECEIVED

JUL 0 6 2016

San Mateo County Planning

Yes	No	Will the project involve:		
	<b>&gt;</b> <	a. Construction outside of the footprint of an existing, legal structure?		
	, SC	b. Exterior construction within 100-feet of a stream?		
	$\times$	c. Construction, maintenance or use of a road, bridge, or trail on a stream bank or unstable hill slope?		
	X	d. Land-use within a riparian area?		
	X.	e. Timber harvesting, mining, grazing or grading?		
	$\times$	f. Any work inside of a stream, riparian corridor, or shoreline?		
	><	g. Release or capture of fish or commerce dealing with fish?		
Pleas	e explain	any "Yes" answers:		
-	-			


3. Na	tional F	ollutant Discharge Elimination System (NPDES) Review
Yes	No	Will the project involve:
		a. A subdivision or Commercial / Industrial Development that will result in the addition or replacement of 10,000 sq. ft. or more of impervious surface?
	*	If yes, Property Owner may be required to implement appropriate source control and site design measures and to design and implement stormwater treatment measures, to reduce the discharge of stormwater pollutants. Please consult the Current Planning Section for necessary forms and both construction and post-construction requirements.
		b. Land disturbance of 1 acre or more of area?
	7	If yes, Property Owner must file a Notice of Intent (NOI) to be covered under the statewide General Construction Activities Storm Water Permit (General Permit) <u>prior</u> to the commencement of construction activity. Proof of coverage under State permit must be demonstrated prior to the issuance of a building permit.

I hereby certify that the statements furnished above and in the attached exhibits present the data and information required for this initial evaluation to the best of my ability, and the facts, statements and information presented are true and correct to the best of my knowledge and belief. If any of the facts represented here change, it is my responsibility to inform the County.

0'		_	
Signed:		Date:	
	(4.1)	Personal and Associated Association and Associ	
	(Applicant may sign)		

#### KICHLER.

Style to live by-



Project	
Туре	
Ordering#	
Comments	

Wesley Collection

Wesly 1 Light LED Outdoor Wall Light in TZT AZT 49278AZTLED (Textured Architectural Bronze)

Product Description: Wesly 1 Light LED Outdoor Wall Light mirrors the lines and shapes found on your contemporary home. The half-moon silhouette at top and bottom is lined with etched glass to shed brilliant light. To finish this sleek look our Wall Light is finished with Textured Architectural Bronze.

Available Finishes

Textured Architectural Bronze PL

ADD TO PROJECT

#### Technical Information

Weight: 2.07 LBS Safety Rated: Wet HCWO: 3.75" Base Backplate: 5.25" Color Rendering Index Color Temperature Range: 3000 Dark Sky: Yes Expected Life Span: 35000 Hours Operating Voltage Range: 100-120Vac Light Source: LED Collection: Wesley Collection


7.00" Width: Height: 7.50" Extension: 4.00" 120V Voltage: Energy Efficient: Yes

Kelvin Temperature:

3000K

Finish:

Textured Architectural Bronze



#### MAGELLAN AVE HALF MOON BAY, CA 94019

SHEET TITLE

EXTERIOR COLORS

048-013-600


OWNER SERHIY KYBYCH

7929 DIAMOND ROCK DR. ANTELOPE, USA 95843

(916) 214-5461

	EXTERIOR COLORS (BY BEHR)			
ID	COLOR	NAME	USAGE	
C1		N360-Z	STUCCO WALL FINISH	
C2		ADIRONDACK BLUE N480-5	STUCCO TRIM, HANDRAIL \$ POST	
CB		Y <i>OG</i> I 5360-5	EXTERIOR PAINTED CEILINGS	
C4		AMAZON BREEZE GR-WO3	DOOR/WINDOW FRAME	

#### FRONT ELEVATION



PLM2016-00280






MAP

NOT TO SCALE







AREA GALGULAT	ens .
DWELLING REQUIRED	3,740 SQFT (48% MAX)
DMELLING PROPOSED	3,739 SQFT (47.98%)
UPPER LEVEL	1,128 SQFT
MAIN LEVEL	2,211 SQFT
GARAGE	400 SQFT
STORAGE	1,743 SQFT
DECKING TOTAL	1,148 SQFT
MAIN LEVEL AT DINING	176 SQFT
MAIN LEVEL AT ENTRY	308 SQFT
UPPER LEVEL	664 SQFT
SITE	1,792 SQFT
TOTAL FOOTPRINT	2.323 SQFT (29.81%)

	COMPLIANCE CODES (AS AMENDE CALIFORNIA AND LOCAL JURISDIC	
T (48% MAX)	2013 CALIFORNIA BUILDING CO	
	2013 CALIFORNIA RESIDENTIAL	CODE
T (47.98%)	2013 CALIFORNIA ELECTRICAL	CODE
	2013 CALIFORNIA MECHANICAL	CODE
	2013 CALIFORNIA PLUMBING CO	ODE
	2013 CALIFORNIA ELECTRICAL	CODE
	2013 CALIFORNIA ENERGY COI	DE
Т	PARCEL NO:	
	048-013-600	
	OCCUPANCY GROUP:	
the title by the state of the title of the state of the s	U,R-3	
т	FIRE SPRINKLERS:	
	YES	
т I	OWNER:	
	SERHIY KYBYCH	IMP
	7929 DIAMOND ROCK DR.	and the second second second
	ANTELOPE, CA 95843	LOWER LEVE
	CCOPE OF WORK	DRIVEWAY

MAGELLAN AV	,
HALF MOON BAY, CA 94019 NEW SFD	

	SHEET INDEX
SHEET	TITLE
A1	COVER SHEET, SITE PLAN
A2.1	GARAGE LEVEL FLOOR PLAN
A2.2	MAIN & UPPER LEVEL FLOOR PLANS
A3	EXTERIOR ELEVATIONS
A4	BUILDING SECTIONS


TOPO	BOUNDARY & TOPOGRAPHY MAP
61	DRAINAGE PLAN
62	EROSION CONTROL PLAN

ALEXMARTYNOVSKIY@GMAIL.COM

DATE

MAGELLAN AVE HALF MOON BAY,CA 9

FACE
2,323 5QFT
360 SQFT
33 5QFT
238 SQFT
2,954 5QFT (37,91%)



RECEIVED

JUL 0 6 2016 San Mateo County Planning Division

1 SITE PLAI
A1 SCALE: 1/8" = 1'-0"

SITE PLAN

PLN 2016-U0280

SCALE: AS SHOWN A1

SIGNATURE


DATE:

DRAWN BY:


ALEX MARTYNOVSKIY

PROJECT #: 15030

09/05/2015



		MINDO	W SCHEDULE	
ם ו		5.6	OPERATION	
	D QTY	MIDTH	HEIGHT	TYPE
В	4	1'-6"	1'-6"	FIXED
AA:	2	1'-6"	44'	FIXED
D	4	2° 2'	· 6'	SINGLE HUNG
्	4	2 <b>2</b> '	5'	SINGLE HUNG
D	6	2° 2'	4'	SINGLE HUNG
E	2	2 2'	17'	FIXED
F	2	2'	5'-6"	FIXED
6	5	2'	7'7'	FIXED
- H	1	2'	2'2'	FIXED
1	1	2 2'	÷6'	FIXED
J	1	2'-6"	4'4'	SINGLE HUNG
K	2	2'-6"	6'	SINGLE HUNG
L	1	2'-6"	1'-8 1/4"	FIXED
M	1	∌' <b>3</b> '	6'	SINGLE HUNG
N	1	<b>3'</b>	· 6'	FIXED
०	2	∃' <b>3'</b>	6'-6"	FIXED
P	1	4'4'	7'	FIXED
୍ଦ	2	⊕¹ <b>5</b> '	3'-6"	FIXED
R	2	⊕¹ <b>5</b> '	6'	FIXED
5	2	ି <b>6'</b>	6'	FIXED
ТТ	1	· 6'	77	FIXED



2 GARAGE LEVEL | FLOOR PLAN

SCALE: 1/4" = 1'-0"


MAGELLAN AVE HALF MOON BAY,CA 9 APN 048-013-600 OMNER SERHIY KYBYCH 1929 DIAMOND ROCK DR. ANTELOPE, USA 95843 (916) 214-5461 SHEET TITLE GARAGE LEVEL I FLOOR PLAN ALEX MARTYNOVSKIY PROJECT #: 15030 09/05/2015 DATE: DRAWN BY: AS SHOWN SCALE:

A2.


Alex Martynovskiy 10100 Countryside May Sacramento, USA 95827


ALEXMARTYNOVSKIY@GMAIL.COM

DATE









LEGEND

SPOT ELEVATION (E)

≥2.4′ SPOT ELEVATION (N)

SURFACE DRAINAGE FLOW

**DOWNSPOUT** 

3" MIN. DIAM. PVC DRAIN PIPE

## GENERAL NOTES

- 1. PLANS PREPARED AT REQUEST OF:
- SERHIY KYBYCH, OWNER
- 2. ELEVATION DATUM: ASSUMED 3. CONTOUR INTERVAL IS 1 FOOT.
- 4. SITE SURVEYED BY P. McNULTY, AUGUST 2015.
- 5. THIS IS NOT A BOUNDARY SURVEY.

DRAINAGE NOTES

1. DRAINAGE INTENT: IT IS THE INTENT OF THE DRAINAGE SYSTEM TO CONVEY ROOF RUNOFF TO A SAFE LOCATION, AND TO MINIMIZE EXCESSIVE MOISTURE AROUND FOUNDATIONS.

2. RUNOFF FROM THE ROOF SHALL BE DIRECTED TO THE DRY WELLS, WITH THE INTENT OF PREVENTING AN INCREASE IN RUNOFF FROM THE PROPERTY. ALL DRAIN LINES SHALL LEAD TO DRY WELLS SHOWN. 4. ALL DRAINAGE PIPES SHALL BE 3" MINIMUM DIAMETER SOLID PIPE, SLOPED AT 0.5%

5. GROUND SHALL SLOPE AWAY FROM FOUNDATIONS AT 5% FOR 10 FEET, WHERE

SPACE PERMITS. 6. IT SHALL BE THE OWNER'S RESPONSIBILTY TO ENSURE THAT ALL DRAINAGE IMPROVEMENTS SHOWN HERON ARE MAINTAINED IN GOOD WORKING ORDER. THIS INLCUDES PERIODICALLY INSPECTING THE STORM DRAIN PIPES FOR SEDIMENT AS WELL AS THE DRAIN INLETS FOR SEDIMENT. ANY BUILT UP SEDIMENT SHOULD BE PERIODICALLY REMOVED TO ENSURE THE DRAINAGE FEATURES FUNCTION AS INTENDED.

GRADING NOTES


CUT VOLUME: 15 CY FILL VOLUME: 5 CY


ABOVE VOLUMES ARE APPROXIMATE AND ARE FOR VERY LITTLE WORK TO BUILD FOUNDATIONS, TO BUILD THE DRIVEWEAY, AND TO SLOPE GROUND FOR PROPER DRAINAGE.


ALL GRADING SHALL CONFORM TO LOCAL CODES AND ORDINANCES.


#### TRAFFIC CONTROL NOTES

1. CONTRACTOR AND WORKERS SHALL PARK ALONG MAGELLAN AVENUE. 2. WHEN TRUCKS PARK IN STREET FOR DELIVERY OF SUPPLIES AND CONCRETE, EVERY EFFORT SHALL BE MADE TO PROVIDE ROOM FOR VEHICLES TO PASS. WORKERS SHALL PROVIDE TRAFFIC CONTROL AT ALL TIMES WHEN ROAD IS PARTIALLY BLOCKED. 3. IF ROAD IS BLOCKED, WORKERS SHALL PROVIDE WRITTEN DIRECTIONS FOR A DETOUR, IF REQUESTED BY A MOTORIST.

















LEGEND			
XXX	X	X	Fence
			Property Line
SSSSSS	SS	SS-	Sanitary Sewer Line
WW	W	W	Water Line
			- Edge of Pavement

SURVEY FOR: Serhiy Kybych

### SURVEY OF:

Lots 16 & 17 Block 6 of R.S.M. Book 3 of Maps pg. 95
SITE ADDRESS: Vacant Lot Magellan Avenue,
Unincorporated San mateo County

A.P.N. 048-013-600 Area = 7,791.68 sq. ft.+/-

#### NOTES

- 1.) Survey shows existing site conditions at the time of the survey. Any Site Plan or Grading Plan has been done by others.
- 2.) The Elevations shown are based upon the NAVD 88 Datum.
- 3.) The nearest fire hydrant and utility pole is located at the easterly corner of Magellan Avenue and Mirada Rd.

BOUNDARY & TOPOGRAPHY MAP

Prepared By:

Pat McNulty

Professional Land Surveyor

1604 Francis Avenue

Belmont, California 94002

650-654-6460

DATE: AUGUST 2015

JOB NO.: 29-15




# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Clean Water. Healthy Community.

## Materials & Waste Management



#### **Non-Hazardous Materials**

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ☐ Use (but don't overuse) reclaimed water for dust control.

#### **Hazardous Materials**

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

#### Waste Management

- ☐ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

#### **Construction Entrances and Perimeter**

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

## **Equipment Management & Spill Control**




#### **Maintenance and Parking**

- ☐ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

#### **Spill Prevention and Control**

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ☐ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- □ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

## **Earthmoving**




- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

#### **Contaminated Soils**

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash.

## Paving/Asphalt Work



- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement.

#### Sawcutting & Asphalt/Concrete Removal


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.

## Concrete, Grout & Mortar Application




- Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

## Landscaping



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

## **Painting & Paint Removal**




#### **Painting Cleanup and Removal**

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer.

  Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste.


  Lead based paint removal requires a statecertified contractor.

## Dewatering



- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.

Storm drain polluters may be liable for fines of up to \$10,000 per day!



El.: 21.21'

1 INCH = 10 FEET

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- · There will be no stockpiling of soil. All excavated soil will be hauled off-site as it is excavated.
  - · Perform clearing and earth-moving activities only during dry weather. Measures to ensure adequate erosion and sediment control shall be installed prior to earth-moving activities and construction.
  - Measures to ensure adequate erosion and sediment control are required year-round. Stabilize all denuded areas and maintain erosion control measures continuously between October 1 and April 30.
- Store, handle, and dispose of construction materials and wastes properly, so as to prevent their contact with stormwater.
- · Control and prevent the discharge of all potential pollutants, including pavement cutting wastes, paints, concrete, petroleum products, chemicals, wash water or sediments, and non-stormwater discharges to storm drains and watercourses.
- · Use sediment controls or filtration to remove sediment when dewatering site and obtain Regional Water Quality Control Board (RWQCB) permit(s) as necessary.
- · Avoid cleaning, fueling, or maintaining vehicles on-site, except in a designated area where wash water is contained and treated.
- · Limit and time applications of pesticides and fertilizers to prevent polluted runoff.
- · Limit construction access routes to stabilized, designated access points
- · Avoid tracking dirt or other materials off-site; clean off-site paved areas and sidewalks using dry sweeping methods.
- · Train and provide instruction to all employees and subcontractors regarding the Watershed Protection Maintenance Standards and construction Best Management Practices.
- Placement of erosion materials is required on weekends and during rain events.
- The areas delineated onh the plans for parking, grubbing, storage etc., shall not be enlarged or "run over."
- Dust control is required year-round.
- · Erosion control materials shall be stored on-site
- · Use of plastic sheeting between October 1st and April 30th is not acceptable, unless for use on stockpiles where the stockpile is also protected with fiber rolls containing the base of the stockpile.
- · The tree protection shall be in place before any grading, excavating or grubbing is started.

DUST CONTROL NOTES

1. Water or cover stockpiles of debris, soil, sand or other materials that can be blown by the wind.

- 2. Cover all trucks hauling soil, sand, and other loose materials or require all trucks to maintain at least 2
- 3. Apply water three times daily, or apply (non-toxic) soil stabilizers on all unpaved access roads, parking and staging areas at construction sites. Also, hydroseed or apply non-toxic soil stabilizers to inactive construction areas.
- 4. Sweep daily (preferably with water sweepers) all paved access roads, parking and staging areas at
- 5. Sweep adjacent public streets daily (preferably with water sweepers) if visible soil material is carried
- 6. Enclose, cover, water twice daily or apply non-toxic soil binders to exposed stockpiles (dirt, sand, etc.)
- 7. Install sandbags or other erosion control measures to prevent silt runoff to public roadways. 8. The approved plan shall be implemented for the duration of any grading and construction activities that generate dust and other airborne particles.

BMP SCHEDULE

1: INSTALL FIBER ROLLS PRIOR TO SITE CLEARING.

2: INSTALL ROCKED CONSTRUCTION ENTRANCE PRIOR TO EARTHWORK FOR FOUNDATION. 3: INSTALL CONCRETE WASHOUT AREA PRIOR TO FIRST CONCRETE DELIVERY.

NOTE: SEE ATTACHED BMP SHEET FOR ALL OTHER ASPECTS OF BEST MANAGEMENT PRACTICES.


### EROSION CONTROL NOTES

FIBER ROLE INSTALL AT LOCATIONS SHOWN. AFIX AS SHOWN IN DETAIL 1 1. GRADING MAY TAKE PLACE DURING WET WEATHER AFTER OCTOBER 1 PROVIDED THE

FOLLOWING PROVISIONS ARE FOLLOWED. 2. NO GRADING SHALL TAKE PLACE DURING RAINY WEATHER OR FOR A PERIOD OF AT LEAST 24 HOURS FOLLOWING RAIN. 3. ALL EXPOSED SOIL SHALL BE TEMPORARILY PROTECTED FROM EROSION WITH JUTE 4. ALL STOCKPILED SOIL SHALL BE COVERED AT ALL TIMES AND REMOVED FROM SITE AS SOON AS POSSIBLE, IF SCHEDULED FOR OFF-HAUL. 5. ALL EXPOSED SURFACES SHALL BE PERMANENTLY PROTECTED FROM EROSION WITH SEEDING AND/OR LANDSCAPING. SEED MIX SHALL BE 75 LB PER ACRE ANNUAL RYGRASS OR APPROVED SUBSTITUTE. SEED SHALL BE COVERED WITH STRAW MULCH AT A RATE OF 2 TONS/ACRE. 6. ROCKED CONSTRUCTION ENTRANCE SHALL EXTEND OVER LENGTH OF DRIVEWAY, 26

FEET LONG BY 18 FEET WIDE AND CONFORM TO THE FOLLOWING: A. THE MATERIAL FOR THE PAD SHALL BE 2 TO 3 INCH STONE. B. PAD SHALL BE NOT LESS THAN 8" THICK. C. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL

SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY SHALL BE REMOVED IMMEDIATELY. D. WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED. IT SHALL BE DONE ON AN AREA THAT DRAINS TO THE CONCRETE WASHOUT AREA. 7. CONCRETE WASHOUT AREA SHALL BE SURROUNDED BY A SINGLE LAYER OF SAND BAGS TO CONTAIN FLUIDS. CHANNEL INTO AREA SHALL BE CLEARED TO ALLOW TIRE





COUNTY'S MAIN POINT OF CONTACT IF CORRECTIONS ARE REQUIRED. NAME: SERHIY KYBYCH TITLE/QUALIFICATION: OWNER

E-MAIL: SSERHIYK@HOTMAIL.COM

USE OF PLASTIC SHEETING BETWEEN OCTOBER 1st AND APRIL 30th IS NOT ACCEPTABLE, UNLESS FOR USE ON STOCKPILES WHERE THE STOCKPILE IS ALSO PROTECTED WITH FIBER ROLLS CONTAINING THE BASE OF THE STOCKPILE.

CONTROL ROSION

SHEET